HMI-01 LABVIEW SCADA SCREEN WIREFRAME CONCEPTUAL FRONT PANEL DESIGN SEE DWG 015 / SHEET 1 OF 3 AND SHEET 2 OF 3

A. HMI MAIN OVERVIEW SCREEN

HMI-01
LABVIEW SCADA MAIN OVERVIEW

MAIN | AUTO | MANUAL | ALARM | TREND | SETTINGS

PLC LINK
CONNECTED / DISCONNECTED
RS-232C / XGT

SAFETY
READY / NOT READY
M0001 / P00 / P07

MODE
AUTO / MANUAL
M0010 / M0011

CURRENT STATE
S10 READY / IDLE
M0100~M0114

ACTIVE ALARM
NO ACTIVE ALARM
D0310 / M0120

PE-01INFEED PRESENT
ON / OFF
P04

SOL-01 CLAMP
OPEN / CLOSED
LS-01 / P08

SORT / OUTFEED STATUS

SOL-02 / LS-02
PASS GATE
COMMAND: OFF
POSITION: HOME
P23 / P09

SOL-03 / LS-03
FAIL GATE
COMMAND: OFF
POSITION: HOME
P24 / P0A

SOL-04 / LS-04
RETEST GATE
COMMAND: OFF
POSITION: HOME
P25 / P0B

PE-03
OUTFEED CONFIRM
STATUS: OFF
P06

TEST RESULT
PASS / FAIL
/ RETEST / WAIT
D0020 / D0021

MTR-01
CONVEYOR MOTOR
RUN / STOP
P20 / P21

TOTAL CYCLE
D0300:D0301

PASS COUNT
D0302:D0303

FAIL COUNT
D0304:D0305

RETEST COUNT
D0306:D0307

READ ONLY STATUS / PRODUCTION SUMMARY

AUTO OPERATION FUNCTIONAL SEQUENCE:
SEE DWG 011 / SHEET 1 OF 2.

B. HMI AUTO OPERATION SCREEN

HMI-01
AUTO OPERATION

MAIN | AUTO | MANUAL | ALARM | TREND | SETTINGS

AUTO COMMAND

START
M0200
HMI_START_REQUEST
START ENABLED WHEN:
SAFETY READY + NO FAULT
+ S10 READY / IDLE

NORMAL STOP
M0201
HMI_STOP_REQUEST
STOP:
ALWAYS ACCEPTED

ALARM RESET
M0202
HMI_ALARM_RESET_REQUEST
RESET ENABLED WHEN:
SAFETY READY
+ FAULT CAUSE CLEARED

HMI COMMAND IS A PLC REQUEST ONLY.
HMI COMMAND SHALL NOT BYPASS HARDWIRED SAFETY.

CURRENT PROCESS DATA

CURRENT STATE
M0100~M0114

TEST RESULT
D0020 / D0021

ACTIVE ALARM
D0310

SELECTED ROUTE
M0020 / M0021 / M0022

MCU HEARTBEAT
D0023

AUTO SEQUENCE STATUS

S10 READY / IDLE → P01 OR M0200 START REQUEST → S20 WAIT INFEED → P04 ON INFEED DETECTED → S30 TRANSFER TO TEST → P05 ON TEST POSITION → S40~S60 CLAMP / TEST

D0021 = 1 TEST COMPLETE → S70 CLAMP RELEASE → P08 OFF CLAMP RELEASED → S80 RESULT DECISION → D0020 PASS / FAIL / RETEST → S81 PASS / FAIL / RETEST GATE

P09 / P0A / P0B GATE POSITION OK → S90 TRANSFER OUTFEED → P06 ON OUTFEED CONFIRMED → S100 GATE HOME → ALL GATES HOME → S110 CYCLE COMPLETE → NEXT CYCLE READY

PLC OUTPUT INTERLOCK / ALARM / TIMER MATRIX:
SEE DWG 011 / SHEET 2 OF 2 AND DWG 012.

HMI TAG / COMMAND / ALARM / LOGGING MAP:
SEE DWG 015 / SHEET 2 OF 3 AND SHEET 3 OF 3.

ACTIVE SETPOINT SUMMARY

TEST POSITION SETPOINT
D0050

MOTOR SPEED SETPOINT
D0051

PROCESS ALARM THRESHOLD
D0052

MODE SELECT
D0053

READ ONLY IN AUTO OPERATION SCREEN
EDIT IN MANUAL / SETUP SCREEN

SHOWN OUTSIDE SCREEN FRAME FOR DRAWING CLARITY.
IMPLEMENT AS RIGHT-SIDE PANEL IN AUTO OPERATION SCREEN.

NO.	DATE	REVISION
A	2026-09-17	INITIAL RELEASE

DWG TITLE
EDS Wafer Map Linked Package
Final Test and Multi-Bin Sorting Cell
SCADA HMI SCREEN WIREFRAME

DRAWN BY: J. H. KO
DATE: 2026-09-17
DWG NO: 016
SHEET NO: 1 OF 3