

INSPECTION ACCEPTANCE

First observe DONE=0 while state60.
Require DONE=1 and response ID=request ID.
Only result1..3 accepted; latch D00102 at60 → 70.
Copy accepted request ID to D00029.

PRODUCTION COMPLETION

Count once at current100 → next110.
32-bit TOTAL / PASS / FAIL / RETEST counters.
Result remains latched until next product or abort.
Next product waits for SIM_IO outfeed pickup.

ABORT AND RECOVERY POLICY			
Override	Next state	Saved alarm	Restart
Safety not normal	0	1	Safety rearm + clear/recovery + RESET + START
STOP / invalid Auto mode in cycle	900	2	Remove cause + recover + RESET + START
Timeout / invalid state/result	900	Fault code	Remove cause + recover + RESET + START

Result route: D00102=1→81 PASS,2→82 FAIL,3→83 RETEST. D00101 is calculated separately, then committed once to D00100.

R0	2026-10-22	FUNCTION RECORD
NO.	DATE	REVISION

DWG TITLE

SEMICON SORTER PROJECT
Final Test and Multi-Bin Sorting Cell

LS PROCESS SEQUENCE AND RESULT ROUTING

DRAWN BY	DATE
J. H. KO	2026-10-14

DWG NO
006

SHEET NO
1 OF 1