SITE AC SUPPLY

L /N /PE
Source fault level /supply
Protection ratings TBD

L/N

MAIN ISOLATION

Q0 all-live isolation
Upstream protection
Selection by actual load

AC BRANCH / PLC-01

LS XBC-DR32H without /DC: AC100..240V body supply.
Dedicated protected L/N branch. Never put body supply on24V bus.

AC BRANCH / PS-01

Planned SMPS /model TBD: AC input /regulated24VDC output.
24V CTRL → sensors/controls; safe ACT via safety output chain.
Rating /overcurrent /inrush /wire size still unselected.

OTHER BRANCHES /PENDING

FX body: supply confirmed from exact model/nameplate before connection.
Motor/drive: actual AC/DC type, ratings and stopping function TBD.
PC/ESP USB power: separate current implementation boundary.

PE continuous / bypass Q0

PE / PROTECTIVE BONDING BAR

Enclosure

DIN rail

Drive/motor frame

Specified PE terminals

PE is not a switched signal return. 0V functional bonding, branch fuses and short-circuit ratings require final equipment/supply calculations.

NO.	DATE	REVISION
R0	2026-10-22	CONCEPT / NOT FOR CONSTRUCTION

DWG TITLE

SEMICON SORTER PROJECT
Final Test and Multi-Bin Sorting Cell

PLANNED AC AND DC POWER DISTRIBUTION

DRAWN BY	DATE
J. H. KO	2026-10-14

DWG NO
018

SHEET NO
1 OF 1